BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate
Item No.

Name of Work:Improvements to Roads and drains at saraipalya and surrounding areas in Ward No.06 Byatarayanapura Sub division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	132.75	KSRRB 300-1. **Earthwork excavation** by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 **(Page No141., I.No.19.1 of KPWD S.R 2015-16).**	Cum	83.16	
2	1434.00	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete. 10cm thick**(Page No 25., I.No.5.31.2 of KPWD S.R 2015-16).**	**Sqm**	794.88	
3	320.10	KSRRB 300-1. **Earthwork excavation** by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 1.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications. MORTH / Chapter 3 **(Page No141., I.No.19.1 of KPWD S.R 2015-16).**	Cum	83.16	
4	554.38	KSRRB M300-14. **Excavation for roadwork in all type of soil with hydraulic excavator of 0.9 cum** bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to the embankment location to a lead of 1.00 km and complete as per specifications. MORTH Specification No.301**(Page No 142., I.No.19.14 of KPWD S.R 2015-16).**	Cum	48.60	
5	2217.50	KSRRB 300-58. **Compaction of original ground** with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. MORTH / Chapter 3 **(Page No 148., I.No.19.64 of KPWD S.R 2015-16).**	Cum	4.86	
6	332.63	KSRB-4-1.3 : Providing and laying in position plain cement concrete of mix M 1:4:8 withOPC cement at 180kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2, No. 12/ Item No. 4.3/ PWD SR 2015-16	Cum	5070.60	

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
7	216.50	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC)for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2015-16	Cum	6332.04	
8	2165.00	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2015-16	Sqm	97.20	
9	227.25	Providing groove cutting for width of 5mm to 100m depth 80mm-100 including cost of cutting machine, generatoe & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot birumen fillars, and filler metal etc., including cost of conveyance of all materials,. Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. No. 187/ Item No. 22.7/ PWD SR 2015-16	Mtrs	138.24	
10	534.75	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 2.00 Km (Page No.123,	Cum	73.36	

Executive Engineer 1/x/16.
Byatarayanapura Division
BBMP, Bangalore - 92

"DTS is Approved"

Chief Engineer
Yelahanka Zone
Bruhath Bangalore Mahanagara
Rangalore 92